


LIFTING





Sunbelt Rentals offers a wide range of quality lifting and material handling equipment for hire and sale from industry leading manufacturers.

We also have one of the most technically experienced teams in the industry who are ready to assist with your lifting equipment needs.



FLG Services are now Sunbelt Rentals Lifting



WELCOME

Our services include:

Hire and sales of globally branded lifting equipment

Inspections, repair and testing of customers equipment available both onsite and in our sevice centres.*

Site inspection and testing of loose and static lifting equipment

Online certificate management

Technical site surveys

Delivery throughout the UK

Full Member of Lifting Equipment Engineers
Association

*Depending on the equipment type.

All our equipment is CE compliant, designed to reduce the health and safety risks from lifting, backed by a full service and maintenance history.

We have one of the most technically experienced teams in the industry, with dedicated personnel who are ready to deal with your lifting and handling enquiries.





PRE-HIRE CHECKLIST

Our pre-hire checklist is available to ensure you hire the correct equipment for the job.

The peace of mind that comes from using Sunbelt Rentals as a supplier with fully maintained and regularly serviced equipment means that you can focus your time on other areas based on the knowledge that your lifting gear requirements are being met by a team of experts.

How to navigate your way around our brochure:

We have colour-coded our application areas to save you time and help you find exactly what you need. Please refer to the product link with each product for associated tackle for your required equipment. There is also a product index to enables you to source the equipment directly.

- 1. WHAT IS THE MAXIMUM WEIGHT OF THE LOAD?
- 2. WHAT HEIGHT OF LIFT OR LENGTH OF ROPE DO YOU REQUIRE?
- 3. DO YOU HAVE AN ADEQUATE AND SAFE SUSPENSION/ ANCHORAGE POINT?
- 4. HAVE YOU CONSIDERED ANY
 RESTRICTIONS THAT MAY AFFECT THE
 EQUIPMENT YOU CHOOSE HEIGHT, WEIGHT, WIDTH?
- 5. HAVE YOU ASSESSED THE LOCATION WHERE THE EQUIPMENT IS TO BE USED?
- 6. WHAT POWER SUPPLY DO YOU HAVE AVAILABLE?
- 7. DO YOU REQUIRE ANY FURTHER EQUIPMENT?



Hoisting



Winching



Jacking



General Tackle



Material Handling



Safety



Load Measurement



Crane Hire and Heavy Lift

Girder Clamps
Girder Trolleys

Digital Load Indicator

HOISTING - HAND OPERATED CHAIN BLOCKS - ELECTRIC CHAIN BLOCKS - PORTABLE HOISTS - MINIFORS - AIR OPERATED HOISTS - LEVER OPERATED HOIST - TIRAK MOBILE WINCH - GIRDER CLAMPS/TROLLEYS - BUILDER/SCAFFOLD HOISTS - PLATE LIFTING CLAMPS - QUICK RELEASE SHACKLES



TIGER LIFTING UK LTD

HAND OPERATED CHAIN BLOCKS 0.5t - 35t SWL Lightweight 3m - 30m height of lift as standard, longer available on request. Heavy duty Report of Thorough Examination Supplied Product Link Product Link Slings Shackles Girder Clamps Girder Trolleys Digital Load Indicator Product Link




0.5t - 10t SWL

Heavy duty

Remote control available

Report of Thorough Examination Supplied



Chain Slings

Wheel Barrow Chain Sling














Easy to erect

Extremely versatile

Report of Thorough Examination Supplied



HOISTING

For larger transportation of materials and for passengers, our dedicated Hoist depots can offer Passenger and Goods Hoists, Goods Only Hoists, Bespoke Hoists and Transport Platforms with up to 3,200kg capacity and dimensions up to 2m wide and 6m long.

Head to www.sunbeltrentals.co.uk for further info.



WINCHING

- TIRAKS
- PULLING MACHINES
- HYDRAULIC PULLING MACHINES
- WINCHES
- SNATCH/REEVING BLOCKS
- CABLE DRUM TRAILER
- · CAPSTAN WINCH
- CABLE ROLLERS







	HYDRAULIC PULLING MACHINES	Product Link
	Pneumatic, Electric and Petrol powered	
	0.8t to 5t SWL	Slings Shackles
1	Suitable for lifting and hauling operations	SHIdCKLES
3	Unlimited rope lengths available	Digital Load Indicator
	Report of Thorough Examination Supplied	





WINCHES	Product Link
0.5t - 10t SWL	
Pneumatic, Electric, Diesel and Petrol powered	Slings Shackles
Diesel and Petrol powered	Digital Load Indicator
Heavy duty	Digital Load Indicator
Lifting and hauling application	Cable Rollers Snatch/ Reeving Blocks
Report of Thorough Examination Supplied	




SNATCH/REEVING BLOCKS	Product Link			
For use with varying diameters of wire rope	Slings			
Increases lifting/hauling capacity	Slings Shackles			
Enables the direction of lift/haul to be changed	Winches Pulling Machines Hydraulic Pulling Machines			
Report of Thorough Examination Supplied				


WINCHING

















_	HYDRAULIC RAMS	Product Link
	Up to 500t SWL	
i	Varying sizes available	
	Hi-flow coupling operation	Manifolds Pumps
	Single acting, double acting, low height, screwed and hollow models available	Hoses Gauges
	Can be used in multiples to suit requirements	Oauges
	Report of Thorough Examination Supplied	









	GAUGE	Product Link
200 SIN EZZ 700*	Allows constant pressure monitoring	
Hi-Force	Accurate to ±1 % of full scale	Hydraulic Ram Hydraulic Pump and Hoses Manifolds
	Sizes to suit various applications	


JACKING



	HYDRAULIC JACKS	Product Link
No. 1	0.5t - 100t SWL	
	Heavy duty	Skoots
	Lifting and hauling application	Pallet Trucks
	Report of Thorough Examination Supplied	

	RATCHET TOE JACKS	Product Link
1	Up to 20t SWL	
and the second s	Portable	Skoots
	Heavy duty	Pallet Trucks
(<u></u>	Report of Thorough Examination Supplied	

[-	TROLLEY JACKS	Product Link
	Up to 10t SWL	
	Smooth lift operation	Pallet Trucks
	Report of Thorough Examination Supplied	





CHAIN SLINGS Product Link Up to 67t SWL Wire Rope Slings Shackles Available from 7mm to 32mm construction Fibre Slings Load Measurement Complete range of hooks available Unlimited leg length Hoisting Report of Thorough Examination Supplied

Chain Size	Grade	Single Leg	Choke Hitch	Choke Hitch Endless Two Leg Three and Four Leg		Two Leg		l Four Leg
mm					0°- 45°	45°- 60°	0°- 45°	45°- 60°
6	10	1.4	1.12	2.2	2.0	1.4	2.9	2.1
8	10	2.5	2.0	4.0	3.5	2.5	5.3	3.8
10	10	4.0	3.15	6.4	5.6	4.0	8.4	6.0
13	10	6.7	5.3	10.6	9.5	6.7	14.0	10.0
16	10	10.0	8.0	16.0	14.0	10.0	21.0	15.0
20	10	16.0	12.8	25.6	22.4	16.0	33.6	24.0
22	10	19.0	15.0	30.4	26.5	19.0	40.0	28.0
26	10	26.5	21.2	42.4	37.1	26.5	55.7	39.8
32	10	40.0	32.0	65.0	56.0	40.0	85.0	60.0


Advice for Use

- · Check the condition of the slings before use
- · Check that the chain legs are not twisted
- · Check that the load is on the centre of the hook and not the tip

DO NOT


- · Do not carry out self repairs
- · Do not use the slings over the maximum permissible limit or specified angle
- Do not shock load
- Do not use chain and accessories outside of temperature range -40°C and +200°C

	Number of Legs										
	Grade	1	:	2	;	3	4	4			
ANGLE	8	90°	0°- 45°	45°- 60°	0°- 45°	45°- 60°	0°- 45°	45°- 60°			
FACTOR	8	1	1.4	1	2.1	1.5	2.1	1.5			
7mm	8	1.50	2.12	1.50	3.15	2.24	3.15	2.24			
8mm	8	2.00	2.80	2.80 2.00 4.25		3.00	4.25	3.00			
10mm	8	3.15	3.15 4.25 3.15 6.70		6.70	4.75	6.70	4.75			
13mm	8	5.30	7.50	5.30	11.20	8.00	11.20	8.00			
16mm	8	8.00	11.20	8.00	17.00	11.80	17.00	11.80			
20mm	8	12.50	17.50	12.50	12.50 26.50		26.50	19.00			
22mm	8	15.00	0 21.20 15.00 31.50		31.50	22.40	31.50	22.40			
26mm	8	21.20	30.00	21.20	45.00	31.50	45.00	31.50			
32mm	8	31.50	45.00	31.50	67.00	47.50	67.00	47.50			











Clevis C hook

Clevis grab hook











Sling hook

Self locking hook

Round Slings

Including colour coded range, woven stripe, showing safe working load. 1 stripe = 1 tonne. Available with Tetra and heavy duty sleeve cover. Manufactured to EN1492-2 as applicable. Report of thorough examination supplied.




Flat Webbing Slings

Including colour coded range, soft eye and metal end fitting rings AL1, AL2, AL3, AL4, AL5. Duplex Manufactured to EN1492-1 as applicable.



	Sling	Type				Working Load Limit				
							8	UU	\triangle	
						Straight	Chocked	Parallel Lift	B =	B =
	Web	bing		Round		Straight	CHOCKEU		0-45*	45-60*
Duplex	Width	Endless	Width		Colour	M = 1	M = 0.8	M = 2	M = 1.4	M = 1
D1	30	E1	30	R1	Violet	1	0.8	2	1.4	1
D2	60	E2	60	R2	Green	2	1.6	4	2.8	2
D3										3
D4	120	E4	120	R4	Grey	4	3.2	8	5.6	4
D5	15			R5	Red	5	4	10	7	5
D6	180			R6	Brown	6	4.8	12	8.4	6
D8	240			R8	Blue	8	6.4	16	11.2	8
D10	300			R10	Orange	10	8	20	14	10
				R12	Orange	12	9.6	24	16.8	12
				R15	Orange	15	12	30	21	15
				R20	Orange	20	16	40	28	20
				R25	Orange	25	20	50	35	25
				R30	Orange	30	24	60	42	30



LARGE DEE SHACKLES C/W TYPE 'A' SCREW COLLAR PIN

- Meets the performance requirements of the withdrawn standard BS 3032
- Material: Carbon Steel C45
- Self coloured and hot dip galvanised finish available
 - Proof load tested to 2 times the SWL
 - Minimum breaking load is 4 times the SWL
- Marked with manufacturers mark, size ID mark and SWL
- Report of Thorough Examination Supplied

W.L.L (tonnes)	A (inches)	B (inches)	C (inches)	D (inches)	E (inches)	Weight (kg/each)
0.25	1/4	3/8	1/2	1	1/4	0.10
0.50	3/8	1/2	3/4	1 1/2	1	0.12
0.75	1/2	5/8	1 1/8	2 1/8	1 1/4	0.29
1.50	5/8	3/4	1 1/4	2 1/2	1 1/2	0.57
2.00	3/4	7/8	1 1/2	2 7/8	1 3/4	0.92
3.00	7/8	1	1 3/4	3 1/4	2	1.59
3.75	1	1 1/8	2	3 3/4	2 1/4	2.12
5.00	1 1/8	1 1/4	2 1/8	4 1/8	2 1/2	3.18
6.00	1 1/4	1 3/8	2 3/8	4 1/2	2 3/4	4.54
7.00	1 3/8	1 1/2	2 5/8	5	3	6.06
9.50	1 1/2	1 3/4	2 3/4	5 3/8	3 1/2	8.74



WE SELL AS WELL

Sunbelt Rentals also offers a wide range of products for sale to meet the needs of our customers who prefer to buy instead of hire.

The sale of lifting gear products is an area where the extensive experience of our staff will ensure you get the right product to facilitate your lifting and safety equipment requirements.


Every piece of equipment we offer is supported by an after-sales inspection and repair service which is based on the proven capabilities and resources which we devote to our own inventory of hire equipment.

Call 0808 196 9493 for sales.

Our range of lifting and safety equipment includes:

- Builders hoists
- Chain slings
- Chain blocks (manual and powered)
- Girder clamps/trolleys
- Fibre slings (duplex/round)
- · Hydraulic jacks and rams
- Inertia reels
- Lever hoists
- Lashing systems

- Machine skates
 - Pallet trucks
 - Sack trucks
 - Safety harnesses/lanyards
 - Shackles
 - Snatch blocks
 - Pulling machines
 - Winches
 - Wire rope slings
 - And much more



GREEN PIN STANDARD BOW SHACKLES WITH SCREW COLLAR PIN

- Grade 6 high tensile steel, quenched and tempered
- Minimum breaking load is 6 times the SWL
- Temperature range -20°C upto +200°C
- Report of Thorough Examination Supplied
- Conforms to EN 13889 and meets the performance requirements of US Fed Spec RC-C-271 Type IVA class 2, Grade A.
- Hot dipped galvanised

W.L.L (tonnes)	a (mm)	b (mm)	c (mm)	d (mm)	e (mm)	f (mm)	g (mm)	h (mm)	i (mm)	j (mm)	Weight (kg)
0.33	5	6	12.5	5	9.5	22	16	41	31	28	0.02
0.5	7	8	17	7	12	29	20	54	40	37	0.05
0.75	9	10	21	9	13.5	32	22	61	49	42	0.1
1	10	11	23	10	17	36.5	26	71	56	49	0.14
1.5	11	13	26	11	19	43	29	80	68	54	0.19
2	13.5	16	34	13.5	22	51	32	91	76	63	0.36
3.25	16	19	40	16	27	64	43	114	93	79	0.63
4.75	19	22	47	19	31	76	51	136	107	94	1.01
6.5	22	25	53	22	36	83	58	157	123	107	1.5
8.5	25	28	60	25	43	95	68	176	141	124	2.21
9.5	28	32	67	28	47	108	75	197	158	137	3.16
12	32	35	74	32	51	115	83	218	176	154	4.31
13.5	35	38	80	35	57	133	92	240	192	170	5.55
17	38	42	89	38	60	146	99	262	208	183	7.43
25	45	50	104	45	74	178	126	314	250	226	12.84
35	50	57	111	50	83	197	138	358	281	250	18.15
42.5	57	65	134	57	95	222	160	414	321	287	26.29
55	65	70	145	65	105	260	180	463	355	329	37.6

Want to buy?

Please contact your local service centre or email productsales@sunbeltrentals.co.uk

GENERAL TACKLE

MODULAR CANTILEVER LIFTING BEAM





DIFFERENT SIZES AVAILABLE ON REQUEST



Product Link







GENERAL TACKLE



Product Link


Slings
Shackles

Digital Load Indicator

Crane Hire



LATTICE ROOF SHEET BEAM Up to 3t SWL Available up to 42m length in 3m sections Lightweight Report of Thorough Examination Supplied Product Link Slings Shackles Digital Load Indicator Crane Hire






CMOD MODULAR LIFTING FRAME	Product Link
Spans 0.5m to 16m	Slings Shackles
Capacities 6t to 140t	
Contact local lifting service centre for bespoke quotation	Digital Load Indicator
Report of Thorough Examination Supplied	Crane Hire


MODULAR SPREADER BEAMS

LOAD V SPAN CHART - MODULIFT SPREADER BEAM

STANDARD RANGE



HEAVY RANGE



WEIGHT PER SET (KGS) * Weight based on heaviest spreader in series using configuration recommended in user instructions

Weight	MOD 6	MOD 12	MOD 24	MOD 34	MOD 50	MOD 70/H	MOD 110/H	MOD 110SH	MOD 250	MOD 400	MOD 600
Max. Component Weight	8.1	19	41	51	140	240	367	444	860	165	2665
Min. Component Weight	0.6	1.3	5	7	11	17/32	4/45	63	90	135	135
Weight at Max. Span	32	75	178	290	532	972/1090	1970/2130	2628	4895	8260	17260

WHAT SIZE SHACKLE DO I NEED?

STANDARD RANGE









Top: 35t

Lower: 25t



MOD 34

Top: 25t Lower: 17t

MOD 6 Top: 4.75t Lower: 3.25t

Top: 8.5t Lower: 6.5t


MOD 24 Top: 17t Lower: 12t

MOD 70/H Top: 55t/85t Lower: 35t/55t


HEAVY RANGE




MOD 110/H/SH Top: 85t/120t/150t Lower: 55t/85t/120t



MOD 250 Top: 200t-300t Lower: 125t-200t



MOD 400 Top: 300t-400t Lower: 200t-400t



MOD 600+ Top: 300t-600t Lower: 200t-500t

STANDARD RANGE - COMPONENTS PER SET * Please note: Custom length Struts are available on request

Canada Custan	Strut											End	Drop		
Spreader System	0.1m	0.2m	0.25m	0.3m	0.5m	0.6m	0.75m	1.0m	1.5m	2.0m	3.0m	4.0m	6.0m	unit	link
MOD 6	1	1		1		1		4						2	2
MOD 12			1		1		1	1	3					2	2
MOD 24					1			1		3				2	2
MOD 34					1			1		4				2	2
MOD 50					1			2		1		2		2	2
MOD 70/70H					1			1		2		2		2	2
MOD 110/110H					1			1		2		3		2	2
MOD 110SH					1			1		1		3		2	2
MOD 250-250/250-300/250-400					1			1		2	1		2	2	2
MOD 400-400/400-500/400-600					1			1		1	1		3	2	2
MOD 600-600/600-800/600-1000					1			1		1	1		3	2	2

MATERIAL HANDLING SKOOTS • GANTRIES · SHEAR LEGS

- CRANE FORKS
- FLOOR CRANES
- PALLET TRUCKS
- ROUSTABOUTS
- VACUUM LIFTS
- MACHINE SKATES
- SHIFTA CONVEYOR

- SPREADER BEAMS
- BLOCK/KERB GRABS
- MATERIAL LIFTS
- BUMPA/HODDI HOIST
- POWERED STAIR CLIMBER
- GLASS HANDLING **MACHINES**
- TRACKED CARRIER





GANTRIES Product Link 0.5t - 20t SWL Adjustable in height and width Report of Thorough Examination Supplied

Hand Operated Chain Hoist Electric Chain Block Portable Hoist, Air Hoist Girder Clamps, Girder Trolleys



ALUMINIUM GANTRIES Product Link Up to 5t SWL Adjustable in height Lightweight Various beam lengths available 3m to 6m span Report of Thorough Examination Supplied

Ideal for use where space is at a premium

1	Slings
(7)	Hand Operated Chain Hoist Electric Chain Block
	Portable Hoist, Air Hoist Girder Clamps, Girder
	Trolleys



RAPIDE GANTRIES	
Upto 500kg	Load bearing, lockable castors for easy positioning
Adaptable, multi-purpose trolleys	Report of thorough Examination supplied
Rapid assembly by one person in less than a minute	Can be used as a rescue frame see page 52 for more information
Winch options available	Harness and lanyard



THE RESERVE	SHEAR LEGS	Product Link
	0.5t - 3t SWL	Chain Slings
1	Adjustable in height and width	Chain Slings Shackles Hand Operat Electric Chai
7	Report of Thorough Examination Supplied	Electric Chai

ated Chain Hoist ain Hoist

TRACKED CARRIERS

The 1200 series Tracked Carriers are the ideal all-round carriers. At just 750mm wide the 1200 R and 1200 PRO models can fit through most doorways, and with a substantial 1,200kg maximum capacity the uses are endless.

Tracked Carriers R models use state-ofthe-art technology whilst being simple to operate, reliable and easy to maintain. PRO models offer increased features such as gradient monitoring, information feedback and a smart auxiliary output, ideal when increased safety measures are required or powered attachments make the job easier.

- · Power (max) 2.4kW
- Battery capacity 115Ah
- Charger input 110v-230v
- Max capacity on level ground 1200kg on page 17

	R Model	Pro Model
Efficient direct AC electric drive		
Fully propportional remote control		
Maintenance free AGM batteries		
Hazard lights front and rear		
Switchable motion alarm		
On board diagnostics		
Adaptable and extendable platform		
LCD information screen on remote control	_	
Smart auxilary output socket	_	
Automatic gradient/speed monitoring	_	
Non-marking tracks		
Wide range of attachments		

Standard

Optional




REID PORTAGANTRY

Dimensions [mm]

MILL Deal	Frame	D Max	E	D Min	F	H Max	H Min	G	A-Frame weight	Trolley	Castor
WLL [kg]	size [Product Code]	Height to lifting eye	Height increment	Height to lifting eye	Height to top of beam	Height to top of roller	Height to top of roller	Width	[kg] (approx)	roller size	Diam
	PGAS00500S	2355	5 x 150	1605	2675	2757	2007	1212	32	82	150
	PGAS00500M	2851	5 x 150	2101	3171	3253	2503	1429	42	82	150
	PGAS00500I	3188	5 x 200	2188	3499	3581	2581	1726	50	82	200
500	PGAS00500T	4079	6 x 200	2879	4399	4481	3281	2011	56	82	200
300	PGAS00500TC4	4527	6 x 200	3327	4847	4930	3730	2234	86	82	200
	PGAS00500TC3	5027	6 x 200	3827	5347	5430	4230	2557	91	82	200
	PGAS00500TC2	5527	8 x 200	3927	5848	5930	4330	2733	97	82	200
	PGAS00500TC1	5829	9 x 200	4029	6149	6231	4431	2733	102	82	200
	PGAS01000S	2355	5 x 150	1605	2675	2757	2007	1212	32	82	150
	PGAS01000M	2851	5 x 150	2101	3171	3253	2503	1429	42	82	150
	PGAS01000I	3188	5 x 200	2188	3499	3581	2581	1726	50	82	200
	PGAS01000T	4079	6 x 200	2879	4399	4481	3281	2011	56	82	200
1000	PGAS01000TC4	4527	6 x 200	3327	4847	4930	3730	2234	86	82	200
	PGAS01000TC3	5027	6 x 200	3827	5347	5430	4230	2557	91	82	200
	PGAS01000TC2	5527	8 x 200	3927	5848	5930	4330	2733	97	82	200
	PGAS01000TC1	5829	9 x 200	4029	6149	6231	4431	2733	102	82	200
	PGAS02000S	2355	5 x 150	1605	2675	2757	2007	1212	35	82	150
	PGAS02000M	2851	5 x 150	2101	3171	3253	2503	1429	42	82	150
	PGAS02000I	3188	5 x 200	2188	3499	3581	2581	1726	50	82	200
	PGAS02000T	4079	6 x 200	2879	4399	4481	3281	2011	56	82	200
2000	PGAS02000TC4	4527	6 x 200	3327	4847	4930	3730	2234	86	82	200
	PGAS02000TC3	5027	6 x 200	3827	5347	5430	4230	2557	91	82	200
	PGAS02000TC2	5527	8 x 200	3927	5848	5930	4330	2733	97	82	200
	PGAS02000TC1	5829	9 x 200	4029	6149	6231	4431	2733	102	82	200
	PGAS03000S	2410	5 x 150	1660	2730	2812	2062	1212	56	82	200
	PGAS03000M	2906	5 x 150	2156	3226	3308	2558	1429	61	82	200
	PGAS030001	3188	5 x 200	2188	3499	3581	2581	1726	73	82	200
3000	PGAS03000T	4079	6 x 200	2879	4399	4481	3281	2011	85	82	200
	PGAS03000TC4	4527	6 x 200	3327	4847	4930	3730	2234	86	82	200
	PGAS03000TC3	5027	6 x 200	3827	5347	5430	4230	2557	91	82	200
	PGAS03000TC2	5527	8 x 200	3927	5848	5930	4330	2733	97	82	200
	PGAS05000IR	3181	5 x 200	2181	3592	3717	2717	1736	99*	125	200
	PGAS05000TR	4049	6 x 200	2849	4487	4612	3412	2021	109*	125	200
5000	PGAS05000TC4R	4500	6 x 200	3300	4938	5062	3862	2234	96	125	200
	PGAS05000TC3R	5000	6 x 200	3800	5438	5562	4362	2557	101	125	200
		S & M ver		ole as custom syste	ems WLL 50	000kg dimensior	ns systems are sho	own using the de	eeper 'D' section b	peam	

Dimensions use standard Master Link Trolley, other options available to increase resulting height of lift (HoL) and to assist with load movement.

REID PORTAGANTRY 500-5000



	Standard Beam Length A[mm] (Clear Operating Span C = A - 920 mm)									
A [mm]	2500	3000	3920	4570	5500	6000	8400	9000		
C [Min] [mm]	1180	1680	2200	2050	2980	3480	5880	6480		
C [Max] [mm]	1580	2080	3000	3650	4580	5080	7480	8080		
500	19	22	29	34	41	44	62	66		
1000	19	22	29	34	41	44	79	84		
2000	19	22	29	34	52	93*	130*	×		
3000	19	22	37	43	85*	93*	130*	×		
5000	39*	47*	61*	71*	85*	×	×	×		

Weight of Beams [kg]

*Clear operating span for D section beams is C = A - 910mm.

To ensure stability of the structure, the operating span of the beam must be equal to or greater than the distance between the castors on the A-frame

^{*}Weight includes stabiliser legs









GML 800+ M-SERIES MATERIAL LIFT

- High safe working loads, versatile applications, ease of operation and durability are some of the most important aspects in the development of the GML800+ range.
- Manual winch, each with worm gear for powerful use or small use of force when cranking.
- The GML800 + series is constructed such that the outriggers can be mounted to the front and to the rear on the chassis. This allows to combine the lift on respective use and local conditions individually

GML 800+ IS AVAILABLE IN

M-Serie	GML800+/10/M	GML800+/15/M	GML800+/20/M	GML800+/25/M
Working height - Standard fork up	3.49m	4.98m	6.46m	7.94m
Transport position - height/length/width	1.98/1.00/0.78m	1.98/1.00/0.78m	1.8/1.00/0.78m	1.98/1.00/0.78m
Working position - height/ length/width	1.98/1.94*/0.78m	1.98/1.94*/0.78m	1.98/1.94*/0.78m	1.98/1.94*/0.78m
Safe working load (load centre at 28 cm)	900kg	850kg	850kg	800kg
Weight Chassis + outriggers	237kg	260kg	293kg	316 kg
Weight - counterbalance weights + box	207kg	207kg	207kg	207kg



Pallet Trucks
Bogeys
Boom Extension
Drum Support Attachment
Platform Attachment
Extension Forks



COUNTER BALANCE MATERIAL LIFT Available in load of 300kg - 450kg Height lifting upto - 6.90m Loading height minimum- 0.27m Height Stowed upto - 2.04m Payload - 300kg Length Stowed upto - 1.02m Weight basic chassis - 204kg Width Stowed upto - 0.80m Working position - 2.20m Weight complete - 332kg





ROUSTABOUT MATERIAL LIFTS	Product Link
Up to 680kg SWL	
Lifting height up to 7500mm	
Dual speed winch	Pallet Trucks Bogeys
One person operation	
Report of Thorough Examination Supplied	

MATERIAL HANDLING

MATERIAL HANDLING



	FORK LIFT EXTENDABLE JIB	Product Link
innimm.	Up to 5t SWL	
3	Extension range up to 3700mm	Skoots Bogeys
	Easy installation	Rack and Pinion Hoist
	Report of Thorough Examination Supplied	

T	ALL TERRAIN PALLET TRUCKS - Powered and Manual	Product Link
	Up to 1.5t SWL	Skoots
	Ideal for uneven surfaces	Bogeys
	Report of Thorough Examination Supplied	Rack and Pinion Hoist

	POWERED PALLET TRUCKS	Product Link
	Up to 2t SWL	
Lindse 7 18	110V/240V charge	Skoots Bogeys
	Labour saving	Rack and Pinion Hoist
	Report of Thorough Examination Supplied	



POWERED PEDESTRIAN OPERATED STACKER TRUCKS	Product Link
Up to 1.2t SWL	
110V/240V charge	Skoots Bogeys
Labour saving	Rack and Pinion Hoist
Report of Thorough Examination Supplied	



 FORK LIFT ATTACHMENTS	Product Link
Up to 5t SWL	
Highly versatile	Chain Slings Slings
Easy installation	Shackles
Report of Thorough Examination Supplied	



RUBBLE TRUCK	Product Link
Max Load 750kg	
Measures 750mm (w) x 1530mm (l) x 930mm (h)	Ω Chain Slings
400Litre Volume	Shackles
Total weight (empty) 67kg	Rack and Pinion Hoist
Report of Thorough Examination Supplied	



	COUNTER-BALANCED HYDRAULIC FLOOR CRANES	Product Link
	0.25t - 1t SWL	Portable Hoist
>	Telescopic lifting points	Hand Operated and Electric Chain Blocks
	Highly manoeuvrable	Slings Shackles
	Report of Thorough Examination Supplied	Shackles



OUT-RIGGED HYDRAULIC FLOOR CRANES 0.25t - 3t SWL Highly versatile Telescopic lifting points Report of Thorough Examination Supplied Product Link Portable Hoist Hand Operated and Electric Chain Blocks Slings Shackles


	MACHINE MOVING SKATES	Product Link
	6t - 100t capacity	Pallet Trucks Skoots Pulling Machines
	Available in caterpillar, roto and nylon models	
	Easy to use	
	Low headroom	Hydraulic Pulling Machines Winches
	Report of Thorough Examination Supplied	Williams

7	2 & 4 WHEEL BOGEYS	Product Link
	Up to 2t SWL	_
1	Turntable operation	Pallet Trucks Skoots
	Varying platform size	Pulling Machines
	Flat top and V-shape 2 wheel bogeys also available	Hydraulic Pulling Machines Winches
	Report of Thorough Examination Supplied	












MATERIAL HANDLING





SHIFTA - PORTABLE CONVEYOR	Product Link
Ideal for use with stones, aggregate, soil, concrete etc	
Maximum payload 150kg	
5kva 110v transformer will run four linked machines	
Max angle 50° depending on material (eg. Stones, aggregate, soil)	Skip Lifting Cradle
In built belt tracking and scraper (scraper front and back)	
Detachable hopper	
Report of Thorough Examination Supplied	

BUMPA/HODDI HOIST	Product Link
Up to 10m operation	
110V availability	O Dannin
Easy Installation	Bogeys Pallet Trucks
Hoddi buckets available to hire/purchase	Starke Bin
Report of Thorough Examination Supplied	



	GEDA 200Z VERTICAL MATERIAL HOIST	Product Link
	200kg SWL	
	Max height of lift 35mtr with option of multiple landing gates	Bogey
GEDA	1.5x 1.5mtr base footprint	Pallet Trucks
	Report of Thorough Examination Supplied	Panel Trolley
	Report of Thorough Examination Supplied	











MATERIAL HANDLING

Designed for the safe lifting of pipes from transport vehicles to the placement within trenches. The RVD-4 can be attached to any lifting device with a quick change facility. Capable of lifting one pipe up to 4.000kg and with diameters of between 300mm to 1.200mm.

Carrying Capacity - 4000kg SWL

Gripping Range - 300mm -1200mm

For use with suitable plant (Quick hitch operation)



a	VACUUM LIFTING EQUIPMENT VH1	Product Link
	Carrying capacity 25kg and 50kg SWL	
	One person operation for lightweight slabs and short transportation distance	Pallet Trucks Bogeys
	Two person operation upto 50kg	



VACUUM LIFTING EQUIPMENT - SH1000	Product Link
Carrying capacity 1000kg SWL	
Petrol powered	Pallet Trucks Bogeys
Various suction plates available for use with suitable plant	

VACUUM LIFTING EQUIPMENT - SH2500	Product Link
Carrying capacity 2500kg SWL	
Petrol powered	Pallet Trucks Bogeys
Various suction plates available for use with suitable plant	









Product Link **EXG EASY GRIP STONE HANDLE** KERB AND SLAB LIFTING EQUIPMENT Pallet Trucks Carrying capacity 500kg swl Gripping range 0mm - 300mm Fork Lift Attachment Two person operations For use with suitable plant



	TSV STEP HANDLES	Product Link	
2	KERB AND SLAB LIFTING EQUIPMENT		
	Carrying capacity 250kg swl	Pallet Trucks	
A	Gripping range 70mm - 500mm	Bogeys	
	Two person operations	Fork Lift Attachment	
	For use with suitable plant		



	TSZ UNI STEP HANDLES	Product Link
	KERB AND SLAB LIFTING EQUIPMENT	
	Carrying capacity 600kg swl	Pallet Trucks
	Gripping range 50mm - 600kg swl	Bogeys Fork Lift Attachment
	For use with suitable plant	



	FTZ UNI 15 CONCRETE GRAB	Product Link
	KERB AND SLAB LIFTING EQUIPMENT	
	Carrying capacity 1500kg	Pallet Trucks
No.	Gripping range 0mm - 750mm	Bogeys Fork Lift Attachment
	For use with suitable plant	



· · · · · · · · · · · · · · · · · · ·	FTZ UNI 50 CONCRETE GRAB	Product Link
Palet	KERB AND SLAB LIFTING EQUIPMENT	
	Carrying capacity 5000kg swl	Pallet Trucks Bogeys
	Gripping range 0mm - 850mm	Fork Lift Attachment
	For use with suitable plant	Crane Hire



To the state of th	SRG UNI MANHOLE RING CLAMPS	Product Link
	For use with suitable plant	Oralie fill e
	Gripping range 900mm - 1800mm (complete with adaptors)	Fork Lift Attachment Crane Hire
	Carrying capacity 2500kg swl	Pallet Trucks Bogeys
	PIPE & MANHOLE LIFTING EQUIPMENT	



	PIPE & MANHOLE LIFTING EQUIPMENT	
SINGRED.	Carrying capacity 1500kg and 3000kg	Pallet Trucks Bogeys
A Linne	1500kg gripping range 400mm - 1200mm	Fork Lift Attachment
KSX17V	3000kg gripping range 600mm - 1800mm	Crane Hire
4	For use with suitable plant	



SDH-H MANHOLE COVER LIFTER	Product Link
PIPE & MANHOLE LIFTING EQUIPMENT	Gas Detector
0	Escape Set
Carrying capacity 1500kg swl	Tripod
	Rapide Gantry
key cover lifter	Safety Harness
	Lanyard
Manual operation	Counter Balance Davit



MATERIAL HANDLING

RG5-150 ROUND PIPE GRAB PIPE & MANHOLE LIFTING EQUIPMENT Carrying capacity 5000kg Gripping range 600mm - 1500mm For use with suitable plant



	SG40 - SG80 SCISSOR GRAB	Produc	t Link
	Carrying capacity 1800kg		
-	Gripping range 500mm - 1100mm		Pallet Trucks Bogeys Fork Lift Attachment
	For use with suitable plant (fork sleeve attachment availble)		Fork Lift Attachment Crane Hire
	Supplied with a rated safety net		orane rine




BZSH SITE FENCE BLOCK LIFTER	Product Link
Carrying capacity 35kg	
One or two person operation	Pallet Trucks Bogeys
For use with suitable plant	



<u>e</u>	H-FVZ BOULDER GRAB	Product Link
OLDBUR	Carrying capacity 200kg swl	
	Gripping range 0mm - 600mm	Pallet Trucks
	Two person operation	Pattet Trucks
	For use with suitable plant	

VTK-V BLOCK CART	Product Link
Carrying capacity 400kg swl	
Gripping range 550mm - 1050mm	Pallet Trucks Bogeys
One person operation	





C. C. Cont.	STONE MAGNET	Product Link
	Carrying capacity 400kg swl	
2	Gripping range 0mm - 550mm	Pallet Trucks
	For use with suitable plant	Bogeys
	Various suction plates available	Slings Shackles
	Wheel kit available	

SAFETY • SAFETY HARNESSES • LANYARDS • FALL ARREST DEVICES • RAPIDE GANTRIES - CONFINED SPACE

Our dedicated Safety & Communications depots can also provide escape sets, gas detectors, defibrillators, winches and much more. Just visit **www.sunbeltrentals.co.uk** for further info.

SAFETY



LANYARDS

Various connectors available

Single or twin leg available

Standard length 2m

Available in restraint or shock absorber designs



Horizontal Safety Line





RAPIDE GANTRIES - CONFINED SPACE	Product Lir
Personnel WLL up to 250kg	
3 Person Fall Arrest to EN795:1997	
Certified as part of an EN363 compliant system.	€ Ha
Atex: Suitable for use in ATEX Zone 2 explosive atmosphere	Es Ga
Lightweight and Portable	Но
Within Manual Handling Guidlines weighing only 33kg	
Report of Thorough Examination supplied	

Harnesses Escape Sets Gas Detector Horizontal Safety Line

LOAD MEASUREMENT DIGITAL LOAD INDICATORS COMPRESSIVE LOAD INDICATORS • TEST WEIGHTS • TEST CRADLES

	DIGITAL LOAD INDICATORS	Product Link
	Up to 100t SWL	
Num 2011550 0	Remote readout available	Shackles
0.000	Compact and lightweight	Hoisting
	Accuracy: ± 0.2% of nominal capacity	Winching
	Report of Thorough Examination Supplied	

LOAD MEASUREMENT





Each stillage can hold 4 no 20kg weights and added to the self-weight of the stillage totals 100kg

Each stillage with weights can then be transported by the trolley and positioned where required eliminating any carrying of the weights

For most hires only one trolley would be required and the respective number of weights and stillages to achieve the required total weight requirement by the customer

Commonly used for all types of testing work





We are proud to offer a variety of Heavy lift and Crane Accessories, including industry changing Modulift Spreader and Lifting Beam range that can offer lifting solutions up to 1000 tonne SWL.

Our range of Heavy Lift equipment is immediately available for hire or supply and our team of experts can carry out site surveys to help find solutions to overcome any Heavy Lift challenge our customers may face.

OUR RANGE OF ACCESSORIES INCLUDE:

- Modular spreader beams up to 1000t
- CMOD Lifting Frame up to 250t
- Widebody shackles up to 500t
- Wire ropes/grommits 600t
- Dyneema ropes and slings
- · Crane accessories and mats
- Active Link drop links with data logging available

OUR SERVICES INCLUDE:

- Bespoke design and manufacture of lifting beams/ accessories
- · Advice on rig planning and full
- Site Surveys

CRANE HIRE



Product Link **G20 PICK AND CARRY CRANE** Up to 2t SWL Portable Hoists Small and compact Electric Hoists Report of Thorough Examination Supplied Slings Shackles Ideal for Curtain Wall installation Battery powered

SPIDER MINI-CRANES
Up to 1t SWL or four men
Compliant to current legislation
Report of Thorough Examination Supplied

SOUR STATE	SPIDER MINI-CRANES	Product Link
A STATE OF THE PARTY OF THE PAR	Up to 1t SWL or four men	Digital Load Indicator
	Compliant to current legislation	Slings
	Report of Thorough Examination Supplied	Shackles



T	CRANE LIFTING ACCESSORIES
M	Up to 100t SWL
	Conventional and all terrain specifications
	Site survey available upon request
C	Banksman/riggers and appointed person supplied if required
	Report of Thorough Examination Supplied



CRANE SKIPS	Product Link
Up to 2000L	Crane Hire
Master flow, geared, rollover and funnel types available	Slings Shackles
Report of Thorough Examination Supplied	Snackles



MAN-RIDING AND STRETCHER CRADLES Product Link Crane Hire Slings Shackle Report of Thorough Examination Supplied




Want to buy?
Email Liftingenquiries@sunbeltrentals.co.uk

BESPOKE DESIGNS AND SOLUTIONS

Sunbelt Rentals is able to arrange the design, manufacture and supply of a wide variety of lifting equipment, working with expert supply partners to ensure our customers get the highest quality and safest equipment every time.

We are always looking for innovation, to develop and adopt new lifting equipment to assist our customers. By working with our expert supply partners, all designs are fully supported by technical files with design calculations and drawings and we have worked alongside many of the UK leading names in Construction, Glass panel installation and Structural engineers.



CASE STUDIES

Client Project Name Location MGA Northwest Limited Birkenhead Bridge Birkenhead, Wirral

THE CHALLENGE

This was a high profile project as there was significant disruption to the travelling public during the dismantling work. The route between Wallasey and Birkenhead is ordinarily very busy and there was no through route along Tower Road during the works, so time was of the essence. The bridge needed to be lifted by a floating crane and lifted over 300 metres to the quayside. With uncertainty relating to the exact weight of the bridge, Sunbelt Rentals were tasked with supplying over 400 tonne of lifting tackle to complete this challenging lift.

THE SOLUTION

Following an assessment of the lift based on the customer's plan, Sunbelt Rentals provided a comprehensive list of all the products and accessories needed to complete the lift successfully. This comprised a floating crane capable of lifting the structure and carrying it across to the quayside. The product range supplied by Sunbelt Rentals included a 400 Tonne Modular Beam, 250 Tonne Dyneema Round Slings, 110H Modular Beams, 58 Tonne Wire Rope Slings, 55 Tonne Collar Chains and Widebody Shackles. Due to the heavy weight of the dismantled steel bridge, Health and Safety was the ultimate priority and Sunbelt Rentals' expertise in the lifting sector was absolutely critical.

THE RESULTS

The lift was successfully completed in a single day with all lifting equipment supplied by the local Sunbelt Rentals service centre in Liverpool. This project showcased Sunbelt Rentals' investment in heavy lifting equipment, and our expertise in completing demanding lifts.



Client Osprey Ltd

Project Name Water for Maiden Voyage

Partner Supplier Modulift

THE CHALLENGE

Osprey accepted a scope of work from shipbuilder Wight Shipyard to move the vessel from the shed where it was built to the water at Venture Quays, Cowes on the Isle of Wight, before a course was set for its final destination in Austria. The 250-passenger Twin City Liner is 39.7m long, 11.1m wide, and 6.8m high.

The first challenge was removing the vessel, which is due to arrive in Vienna in time for the start of the new season at the end of March 2019 from its building. Osprey selected two, six-axle Goldhofer self-propelled modular transporters (SPMT) to work in tandem to move the load to within the reach of the Liebherr LTM1800D. The crane was complete with a 36m high rig, designed to accommodate a 3.7m centre of gravity offset and different elevations of the boat's lifting eyes.

THE SOLUTION

A Modulift MOD400 was used at a 29m span beneath 29m long and 26.4m long top slings to balance the lift, these Dyneema and polyester slings also provided by Sunbelt Rentals. Two MOD70H beams were used underneath, one at 5.5m long and the other at 4m. Again, two different lengths of sling were used to connect them to the top beam—3m at the stern (back) and 3.9m at the bow (front). The slings that met the lifting eyes at the bottom of the rig were all 4m in length.

Danny Skidmore, heavy cranes manager at Osprey, said: "We had to work closely with shipbuilders and naval architects, and refer to CAD (computer-aided design), to devise a method of lifting the catamaran safely and completely level. The previous time we lifted such a vessel, we used two cranes in tandem, but mobilising two cranes of that size represents a large-scale operation and high costs, not to mention the disruption it has on the shipyard. We wanted to come up with a way to minimise mobilisation and limit the impact on our client's busy, marine environment."



CASE STUDIES

Client
Project Name
Location

NG Bailey
Custom Electric Stackers
The Forge, 105 Sumner Street, London

NG Bailey is the UK's leading independent engineering and services business, bringing buildings and infrastructure to life. One of their latest projects is a multi-level development in Central London called The Forge. The Forge is two newbuild commercial office buildings, built around a publicly accessible internal courtyard, in total comprising c. 139,000 sq ft. It will be nine storeys high with reception and basement areas. The development will be a high quality and sustainable building with a vastly improved streetscape and public realm. NG Bailey approached Sunbelt Rentals during the early stages of the project to support with developing a solution to safely lift and install pre-assembled modules. The modules were manufactured off-site and contained all of the electrics and pipework needed during the construction of the development.

THE CHALLENGE

NG Bailey had initially planned on using standard stackers to lift the modules into place, however this presented a number of challenges.

The stackers needed to be a net weight of less than 2,000 kg to be transported using a goods lift between floors. Standard forks wouldn't be long enough to lift the modules into position, however adding extension forks would have gone against the manufacturer's recommendation, so wasn't an option.

With a challenging set of project constraints, it was great to see Sunbelt Rentals understood our needs both on paper and on site. Since using the custom stackers, we have increased our module installation productivity and made the installation process safer due to the extended forks.


Chris Baggley, Project Engineer, NG Bailey

THE SOLUTION

Working closely with our supplier, SHS Handling, Sunbelt Rentals developed and engineered a custom solution, an extended fork electric stacker. The weight of these custom designed stackers was kept below 2,000 kg so they could use the goods lifts on site, they also gave NG Bailey maximum clearance between the forks and mast so the modules could be positioned correctly. The solution was engineered, manufactured and delivered to site within 12-weeks.

THE RESULTS

Sunbelt Rentals invested in four of the custom designed stackers and supplied them to the site in early September ensuring NG Bailey were able to complete that phase of the project safely, on schedule and without disrupting the wider site. The stackers are now on long-term hire with NG Bailey.





INSPECTION AND TESTING

Sunbelt Rentals are full members of LEEA (Lifting Equipment Engineers Association), giving you peace of mind that all your lifting needs are being met by a team of experienced personnel.

All of our lifting and safety equipment is CE compliant and we also offer a full maintenance and aftersales service for your own equipment, giving you the confidence that your owned equipment is also legally compliant.

Sunbelt Rentals are able to carry out Thorough Examination of fixed and loose lifting equipment on site or at your own premises. Once compliant we can advise you on certification maintenance such as Colour Coding and also give you the capability to review your Reports of Thorough Examination online.

inspections@sunbeltrentals.co.uk 0330 1757 308

PROVIDING RENTAL PRODUCTS AND MANAGED SOLUTIONS INTO EVERY MARKET AND SECTOR



Powered Access

The combined height and reach of our equipment can transport you safely over 50,000 metres



Lifting

Our solutions have been used on 7/10 of the tallest buildings in the UK



Energy

From fuel saving cleaner energy solutions to the latest stage v generators, we have a temporary power solution for every site.



Tools

From battery powered hand tools to compressors, compactors and cleaning equipment we offer a wide range of tool hire that's local to you



Plant

The widest range of plant including the latest stage v and battery powered machines in the UK



Plant Attachments

The sole UK distributor for several of the world's leading attachment manufacturers



Surve

Industry-leading supplier of land survey and precision measurement technologies



Test & Monitoring

Europe's leading test equipment specialists since 1996



Non-Mech

Essentials for every site; fencing, barriers, trenching, ground protection, vehicle and pedestrian control solutions



Industrial

On your site to meet the demands where every second counts



Rail

We support the Network Rail and Transport for London infrastructure



Utilities

The UK's largest specialist Utility hire company



Hoists

We hold over 10km of mast sections, enough to scale London's Shard building over 32 times



Safety & Communications

Knowledgeable and experienced specialists in this field



Formwork & Falsework

We are the exclusive hire supplier of MEVA products in the UK $\,$



Trakway

Award winning engineered access and ground protection solutions



Training

Dedicated Health and Safety training to qualify our own people and our customer's people



Traffic Management

24/7 national coverage with operations covered by QEHSS accreditations



Lighting

The UK's largest fleet of state-of-the-art tower lights, including a wide range of solar, hybrid and plug-in options.



Barriers & Fencing

Crowd control and perimeter security solutions



Climate Control

Economical and efficient temperature control and HVAC solutions



Production

From cameras, grip and lighting to backlot infrastructure



Accommodation

24/7/365 call out facility covering 20,000 items on fleet

DEPOT CONTACTS AND LOCATIONS

EAST LONDON

Unit D3, Star Business Centre, Marsh Way, Fairview Industrial Estate, Rainham, Essex RM13 8UP 0845 872 5605

IPSWICH

Unit 5, Boss Hall Business Park IP1 5BN 0845 872 5609

WEST LONDON

Unit 1, Abenglen Industrial Estate, Betam Road, Hayes, Middlesex UB3 1SS 0845 864 3413

BRIDGWATER

Unit 3, Wylds Road, Bridgwater, Somerset TA6 4LF 01278 410 755

WEST MIDLANDS

Units A-C, 100 Dudley Road East, Oldbury, West Midlands B69 3EB 0121 544 1333

EGREMONT

Unit 8, Bridge End, Egremont, Whitehaven CA22 2RD 01946 823905

MANCHESTER

Jardine Way, Chadderton, Oldham, Manchester OL9 9QL 0161 745 9237

LIVERPOOL

Unit 10, King Edward Industrial Estate, Gibraltar Row, Liverpool L3 7HJ 0151 236 2260

SHEFFIELD

Unit 1, Brooklands Business Park Leigh Street, Sheffield S9 2PR 0114 243 0230

HULL

310 Hawthorn Avenue, Hull HU3 5JF 01482 322120

GRIMSBY

Unit 1, Estate Road No.6, South Humberside Industrial Estate North East Lincolnshire DN31 2TG 01472 352 845

GATESHEAD

18D Follingsby Park, Gateshead, Tyne and Wear NE10 8YF 0191 417 6488

WILTON

Castleton Court, Wilton International, Redcar, Teesside TS10 4RG 01642 457325

GLASGOW

1 Earl Haig Road, Hillington Park Glasgow G52 4JU 0141 810 2938

NEWARK

Brunel Drive, Newark NG24 2DE 01636 677 121

FAWLEY

Rigging Loft, Block 3 CMB Fawley Refinery, Fawley S045 1TX 02382 148356



Hire liftingenquiries@sunbeltrentals.co.uk 0330 175 7308

Sales productsales@sunbeltrentals.co.uk 0808 196 9493

Inspections inspections@sunbeltrentals.co.uk 03301757308

www.sunbeltrentals.co.uk