



How we enabled safe site access

Sunbelt Rentals designed and installed a temporary access solution to enable refurbishment of a mobile phone tower at Slough Rugby Club. By protecting the rugby pitches and stabilising access across a deteriorating culvert, heavy vehicles and a 55-ton crane were able to reach the site safely without damaging the surrounding grounds.



Reduced risk of further culvert deterioration



300m of aluminium trakway installed



55-ton crane safely supported



Zero damage to rugby pitches



1 temporary trench crossing installed

WHP Telecoms needed to carry out refurbishment work on a mobile phone tower located within the grounds of Slough Rugby Club.

Sunbelt Rentals were involved from the initial planning stage to provide a solution to gain access to the tower.

Challenges

A lorry and a 55-ton crane were required to enable the refurbishment work to take place. The vehicles needed to travel across the grass rugby pitches and over an existing, crumbling culvert to reach the tower. It was essential that the vehicles did not cause any damage to the area.



Solution

Following an initial site visit to identify the access point and assess ground conditions, Sunbelt Rentals designed and installed a temporary access solution.

Three hundred metres of aluminium trakway panels were laid to protect the rugby pitches while allowing heavy vehicles to move safely across the site. A trench crossing was also positioned across the culvert to prevent further crumbling and provide safe passage.

Additional aluminium trakway panels were then installed to create a stable crane working area, providing sufficient space for the refurbishment work to be carried out safely.

Result

The temporary access solution protected the rugby pitches from damage while enabling heavy vehicles and crane equipment to reach the work area safely.

The trench crossing helped stabilise access over the culvert, reducing the risk of further deterioration, while the crane setup area provided a safe and practical working platform for the refurbishment works to be completed efficiently.

Our equipment and services supplied at a glance

- 300m Aluminium Trakway
- Aluminium Trench Crossing
- Crane Working Platform
- Temporary Access Route

“ The service provided by Sunbelt Rentals has been excellent. The supplied equipment has been perfect for our requirements and allowed us to access the tower easily. ”

Daniel Goodbourn

Build Manager, WHP Telecoms Ltd



Protected valuable playing surfaces

Created safe temporary access

Enabled refurbishment without disruption

Leave the how to us.